the Barr Guards attached to the Sri Chamarajeswaraswami Temple at Chamrajnagar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 (two hundred only) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for construction of qurters for the Barr Guards attached to the Sri Chamarajeswaraswamy Temple at Chamrajnagar", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for item of work.

Abstract estimate for constructing Barr Guards quarters for 4 blocks attached to Sri Chamarajeswaraswami Temple at Chamrajnagar.

No.	Particulars	Per	Quantity
	Details for one Block.		
1	Earthwork and filling in basement	C.yd.	35
2	Burnt brick in mud	C.ft.	3,697
3	Jungle wood doors including painting, complete ...	S.ft.	144
4	Do windows with iron bars including painting	,,	48
5	Burnt stone slabs (6" thick)	,,	72
6	Matti wood including wood oiling	C.ft.	54·41
7	Roofing with first class Mangalore tiles on teak reepers ...	Sqr.	14·56
8	Providing and fixing ridge tiles set in mortar ...	R.ft.	56
9	Plastering with mortar	Sqr.	52·21
10	Coping with burnt brick in mortar and chunam plastering ...	R.ft.	93
11	Ventilating tiles	No.	8
12	Clearing site and levelling ground and contingency ...	Lump	sum
13	Constructing two latrines (one for males and the other for females).	Do	do

N. G. KRISHNA IYENGAR,
Executive Engineer.

SHIMOGA DIVISION.

Notice dated the 27th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 20th October 1929, for restoring Toppengatta Gowdankere Regd. No. 486 Shimoga Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Toppengatta Gowdankere Regd. No. 486, Shimoga Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Thoppingatta Gowdankere Reg. No, 486 in Shimoga Taluk.

No.	Items of work	Per	Quantity
	Bund.		
1	Jungle clearing and rooting out jungle on the bund and slopes	Lump	sum
2	Removing the out hill on the bund and repacking the same with sand.	,,	,,
3	Earthwork for raising bund including watering and tamping, complete.	C.yd.	2,544
4	Turfiing the front and rear slopes of bund ...	Sqr.	311·27
5	Providing and fixing Reg. No. and date stone ...	No	1
6	Do B M stone	,,	2
7	Do Grade stones with bed slabs including cutting figures and painting.	,,	18
8	Providing Top width stones	,,	18
	Constructing a pipe sluice No. I at C. S. O.		
1	Cutting open the bund	C.yd.	93
2	Refilling the above with 10 per cent of earth for settlement ...	,,	100
3	Earthwork excavation	,,	8
4	Concrete in surki mortar	C.ft.	218
5	Burnt stone in surki mortar	,,	289
6	Pointing with surki mortar	Sqr.	4·00
7	Burnt stone slabs 6″ thick roughly dressed and fixed	S.ft.	63
8	Making plug holes and vent way in slabs ...	Lump	sum
9	Providing plug with iron rod, etc., complete ...	,,	,,
	Constructing pipe sluice No. 2 at C. S. No. 8		
1	Cutting open the bund	C.yd.	100
2	Refilling the above with 10 per cent of earth settlement ..	,,	110
3	Earthwork excavation	,,	8
4	Concrete in surki mortar	C.ft.	217
5	Burnt stone in surki mortar	,,	289
6	Pointing with surki mortar	Sqr.	4·00
7	Burnt stone slabs 6″ thick roughly dressed and fixed ...	S.ft.	63
8	Making holes and vent way in slabs ...	Lump	sum
9	Providing plug with iron rod, etc., complete ...	,,	,,
	Constructing Masonry weir 40 feet long at the R. F.		
1	Earthwork excavation	C.yds.	28
2	Burnt stone in surki mortar	C.ft.	338
3	Pointing with surki mortar	Sqr.	2·00
4	Burnt stone slabs 6″ thick dressed and fixed... ...	S.ft.	87
5	Providing joggles	No.	6
6	Rough stone work	C.yd.	26
7	Draft clearing	Lump	sum

Dated 27th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executiv Engineer, Shimoga Division, up to 20th October 1929, for completing the Incomp ete Middl School at Kotehall village, Channagiri Taluk. An app oximate estimate of quantities i given below. These quantities are not guaranteed. The work should be completed by th end of February 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer' Office at Shimoga between the hours of 11 A.M. to 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for completing the Incomplete Middle School at Kotehall village, Channagiri Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

Abstract estimate of quantities for completing the Incomplete Middle School at Kotehall village in Channagiri Taluk.

No.	Items of work	Per	Quantity
1	Earthwork excavating foundation for proposed cross wall ...	C.yd.	3
2	Filling in foundation in rough stone in clay	C.ft.	83
3	Trap stone in clay for basement	,,	60
4	Burnt brick in mortar	,,	418
5	Burnt brick in clay	,,	192
6	Burnt stone slabs dressed 5" to 6" thick	S.ft.	63
7	Honne wood battened shutters to doors including hinges, tower bolts, excluding frames.	,,	128
8	Honne wood battened shutters to windows with hinges, etc., ...	,,	176
9	Honne wood new door with battened shutters with hinges, etc., complete in the proposed new wall.	,,	23
10	Circular ventilators in front and rear gables	No.	4
11	Honne wood work wrought and put up with wood oiling ..	C.ft.	170 37
12	Roofing with 1st class Mangalore tiles on teak reepers ...	Sqrs.	20·16
13	Plastering with mortar	,,	63·04
14	Flooring with gravel	,,	15·37
15	Pointing with mortar	,,	4·22
16	Chacolate painting two coats to doors	,,	7·27
17	White washing two coats	,,	63·04
18	Colour washing two coats	,,	22·45
19	Constructing binding walls	R.ft.	123
20	Cut stone corbels for the verandah	No.	5
21	Teakwood finials	,,	2
22	Teakwood plain eave boards 9"×1"	R.ft.	43
23	Ridge tiles set in mortar	,,	112
24	Zincsheets for valleys with teak wood planks underneath including cement valleys.	,,	68

Notice dated 27th September 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 20th October 1929, for repairing Sri Ranganathaswami Temple at Sorab. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for repairing Sri Ranganathaswami Temple at Sorab in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for repairing "Sree Ranganathaswami Temple" at Sorab, Shimoga District.

No.	Items of work	Per	Quantity
1	Removing the pot tiled roof with jungle wood ...	Sqr.	21·67
2	Dismantling the old mud wall and removing it to a distance ...	C.ft.	3,375
3	Earthwork excavation	C.yd.	25
4	Filling in foundation with laterite brick in clay ...	C.ft.	883
5	Do superstructure do	„	1,133
6	Fixing jungle wood pillars in place of old rotten ones ...	No.	8
7	Providing jungle wood ceiling planks	S.ft.	756
8	Removing and refixing old ceiling planks	„	252
9	Chunam pointing	Sqr.	14·93
10	Jungle wood work honne or nandi wrought and put up, ...	C.ft.	77·57
11	Labour charges for old work	„	25·85
12	Roofing with first class Mangalore tiles on teak reepers ...	Sqr.	15·90
13	Ridge tiles set in mortar	R.ft.	98
14	Jungle wood eave board	„	156
	Miscellaneous.		
1	Chunam plastering with cement rendering including grouting in cement.	Sqr.	3·20
2	Removing the pot tiled reroofing with new bamboos and jungle wood poles.	„	3·36
3	Providing a pillar to support the roof of Archaka's house ...	No.	1
4	Gravel flooring	C.yd.	36
5	Labuor charges for providing a beam	R.ft.	6
6	Repairing the roof of pot tiled of Archaka's house ...	Sqr.	4·10
7	Repairing the mud wall near the well	Lump	sum
8	Providing a door in the compound by the side of Archaka's house.	S.ft.	18
9	Gravelling the ground alround the main temple ...	Lump	sum
	Consructing a compound wall with available materials.		
1	Removing the old mud wall and laterite stones ...	C.ft.	2,180
2	Cut laterite stone in mud new	„	905
3	Do old	„	2,712
4	Do coping in clay	„	345
5	Clearing the vegetation growth	Lump	sum

M. A. SRINIVASACHARI,